

# Vacuum Jacketed Wall Pass Through Piping, Cat# QC-501

Includes

- (2) 1/2" Male CGA296 at end connections
- (2) 1/2" x 2" Long Heat Path Vacuum Breaks
- (2) 4 1/2" round disk wall covers, one welded in place, one shipped loose (note change from drawing detail 3)

MAWP=150 psig@LN2 service

All VJ piping designed and inspected in accordance with ASME B31.3 for normal fluid service

Lead times are 4-6 weeks.

